1 **EXHIBIT 39** 2 3 35-105 Consistency with Master Plan 4 5 The master plan policies were adopted by the planning commission as Resolution 6 xx01 Number 97-05-01 on May 14, 1997, and by the city council as Ordinance Number 86100 7 on May 29, 1997. The master plan policies are intended to provide guidance in the 8 evaluation of future decisions relevant to city planning. The master plan policies do not 9 constitute a substantive change in existing ordinances of the city neither does it 10 supersede nor replace the Unified Development Code or any regulatory ordinance 11 12 adopted prior to the adoption of the master plan policies. Any amendment to the Unified 13 Development Code or other regulatory ordinances made necessary in order for said 14 regulations to be consistent with the master plan policies shall be implemented pursuant 15 to the process prescribed in the master plan policies, in lieu of any provision of this Code 16 in apparent contradiction. 17 18 19 35-105 Consistency with Master Plan 20 Any neighborhhod plan adopted pursuant to 35-420 ofthis 21 (b) 22 chapter. 23 24 xx02 Master plan elements are authorized under Article IX of the City Charter, Section 121. 25 The Master Plan: "The commission may adopt the master plan as a whole or in parts, 26 and may adopt any amendments thereto." Currently adopted master plan elements 27 include those listed below. 28 29 **xx03** Transportation Plan/Major Thoroughfare Plan. (1) 30 31 The Transportation Plan/Major Thoroughfare Plan was adopted by Resolution Number 78-07-02 of the planning commission on July 12, 1978 and adopted as Ordinance 32 Number 49818 by the city council on September 21, 1978. It contains the city's 33 34 transportation policies and the areawide transportation planning process and how it 35 relates to that of the city. 36 37 xx04 (2) Land Use Plan. 38 39 The Land Use Plan was adopted by planning commission Resolution Number 83-05-04 40 on May 25, 1983 and by the city council on December 8, 1983, Ordinance Number 41 83-58-102. The Land Use Plan includes land use objectives and policies for six major 42 components: natural resources: utility infrastructure: transportation corridors: urban form: 43 regulatory measures; and annexation, public facilities and services. 44 45 xx05 (3) **Neighborhood Planning Process.** 46 47 The Neighborhood Planning Process was adopted by the planning commission as 48 Resolution Number 82-10-01 on October 20, 1982 and by city council Ordinance Number 49 57068 on June 2, 1983, for the purpose of providing a vehicle whereby neighborhood 50 residents and property owners could organize to develop a neighborhood plan suitable 51 for official recognition by the planning commission and the city council. Neighborhood 52 planning teams can use this process to " . . . identify issues that will affect their 53 neighborhood's future and select actions for solving (or ameliorating) problems." 54

55

xx06

(4)

Parks Plan.

Adopted by city council Ordinance Number 54605 on November 24, 1981, the Parks Plan was prepared as a joint effort between the department of parks and recreation and the department of planning. The Parks Plan is summarized by a single goal: "Every citizen of San Antonio should have the opportunity to avail themselves of quality parks and recreation facilities and services."

xx07 (5) City Water Board Master Plan.

The waterworks master plan is the "Report on Master Plan for Water Works Improvements" dated September 1981 and subsequent revisions thereof. This adopted plan is implemented through the "Regulations for Water Service" adopted November 20, 1984 by the Board of Trustees, on June 12, 1985 by the city planning commission, and by Ordinance Number 60959 on June 27, 1985 by the city council.

xx08 6) Wastewater Facilities Plan.

The Wastewater Facilities Plan consists of sets of wastewater service policies and sewer extension policies. The SAWPAC report included policies which have been implemented; many have been written in the subdivision regulations.

xx09 (7) Drainage master plans.

As the city continues to define and adopt drainage master plans for specific watershedscontained in whole or in part within the city limits and its ETJ, development will be required to conform to the elements of the plan for each particular watershed. The preservation of the inherent characteristics of natural drainage features and of the natural floodplain where practical is an adopted goal of each watershed drainage plan. The guidance for the drainage master plans was provided by the drainage regulation review committee in February 1996. The first two (2) goals stated in the report are to "Ensure that stormwater management considers and provides reasonable safety from flood hazards for people and property" and to "Integrate stormwater management with natural resource enhancement and protection, compliance with environmental regulations and with creating appropriate development." The drainage master plans developed by the city for each watershed provide long-range guidance for managing the stormwater from existing and future land uses in the most efficient ways possible, with consideration for continued development, reduced flooding potential, adequate stormwater conveyance, increased aquifer recharge, water quality, habitat protection, and increased recreational opportunities.

xx10 (c) Requirements for conformity with the master plan.

This section coordinates the various citations within the Unified Code of Development Regulations that refer to the master plan. It is anticipated that with additional reference to the city's master plan and requirements for conformity, the city will see a genuine effort toward implementation of the plan and its elements.

- (1) Preliminary overall area development plans (POADP) shall conform to the maste plan.
- (2) Subdivisions shall conform to the master plan and the parts thereof.
- The zoning regulations and districts as established in this chapter have been made in accordance with a comprehensive plan.

1 2 3 4 5 6		(d)	council recomn	ning commission, in those instances wherein special approval of city is required, shall consider each such proposed use and make its mendations to the city council with reference thereto including its mendation, among other things, as to proper location with respect to the plan.
7 8 9	xx11	++++ 35-11		++++++++++++++++++++++++++++++++++++++
10 11 12 13 14 15 16 17	xx11	his ass city ma referen	istants, on nager and ce there on the comment seemed and comment seement seeme	tive official for the purposes of this chapter shall be the city manager and deputies, and department heads insofar as they may be charged by the nd the provisions of this chapter with duties and responsibilities with to. Without limitation, the directors of planning, public works, and ervices shall ordinarily administer and enforce the provisions of this
19 20	xx12	++++ 35-30		++++++++++++++++++++++++++++++++++++++
21 22 23 24 25	XX12			s herein established shall apply uniformly to all geographical areas having ct classification and bearing the same symbol or designation on the official
26 27	xx13	+++++	+++++	+++++++++++++++++++++++++++++++++++++++
28 29 30 31			"CBD N	Map Insert"
32 33 34	xx14	+++++ 35-33 (c)		++++++++++++++++++++++++++++++++++++++
35 36 37 38 39 40 41	xx14	except VI, Divi associa	in comp sion 6 of ated lime ations a	established, and no development activity shall occur, within the ERZD liance with the Edwards Aquifer Protection Standards (chapter 34, Article of the city Code). For subdivisions constructed over Edwards and estone formations, all construction shall meet the herein referenced city and the latest revision of the Texas Administrative Code, 31 TAC 313.1-
43 44 45	xx15	& xx16 35-33		++++++++++++++++++++++++++++++++++++++
46 47	xx15	(a)	Devel	lopment standards.
48 49 50 51 52		(1)	with the herein.	al. Ordinances establishing specific urban corridor districts shall comply e requirements addressed in this section subject to the guidelines include In event of a conflict between the specific corridor ordinance and other ons of this Code, the urban corridor provisions shall prevail.

1 2 3 4 5 6 7		(2)	accord accour corrido require	cks. The setback along designated street corridors may be established in lance with the table below. The determination of the setback shall take into not lot size, easements, and the location of existing buildings within the or. All other setbacks shall comply with the base zoning district ements. However, residential buildings less than four (4) stories in height have no greater setbacks than required by the base zoning district.
8 9			С	ollector street 030 feet
10 11			A	rterial street 040 feet
12			E	xpressway 060 feet
13 14		(3)	Reser	ved.
15 16 17 18 19 20		(4)	design view a areas	ning. The following uses may be required to be screened from a lated street corridor to a height sufficient to completely screen the use from t ground level: all outside storage and industrial activities, off-street loading as required by Division 9 of this article, refuse storage areas, air coning and heating equipment, and microwave and satellite antennas.
21 22 23 24		(5)	each s	ways. The total width of driveways shall not exceed forty (40) percent of street frontage, but in any event no less than one (1) driveway shall be ted per platted lot.
25 26 27 28 29 30 31 32		(6)	corrido ordina to an u undero agenci	facilities. Public agencies are encouraged to take into account an urban or designation and be sensitive to the intent and provisions of a corridor nace in the siting and design of facilities which are located within or adjacent urban corridor district. On-site utilities may be required to be located ground unless required by theutility to be otherwise located. Public lies which own property within an urban corridor district are also raged to provide landscaping along public rights-of-way.
33 34 35 36 37 38 39		(7)	adjace easem develo	rocal access easements. Reciprocal access easements between ent properties for use by the general public are encouraged. Where such the plants are platted between adjacent developments and the owners of the expension mutually agree to allow reciprocal parking, a reduction in off-street grequirements may be granted.
40		(b)	Site F	Plan.
41 42 43 44 45 46 47 48 49 50	xx16	(1)	submit occupa exceed (4) cop and or	lan. A site plan for all properties within an urban corridor district shall be sted in conjunction with an application for a building permit or certificate of ancy. The plan shall be on a standard drawing sheet of a size not to district twenty-four by thirty-six (24 X 36) inches and shall be submitted in four pies, including one reproducible copy, together with a reproducible eight ne-half by eleven (8.5 X 11) inches reduction of the plan. The site plan include the following information as applicable for a particular urban corridor to
51 52 53			A.	Street address, legal description, vicinity diagram, scale, north arrow, and perimeter boundaries.
54			B.	Location and dimensions of existing and/or proposed structures,

easements, driveways, and parking areas.

55 56

1 2			C.	Reserved.
3 4			D.	Location and height of required screening.
5			E.	Location and dimensions of proposed signs.
6 7 8 9 10 11		(2)	staff for	onsideration. Upon submission, each site plan shall be reviewed by the recompliance with the standards of the corridor zoning district. If approved, in shall be so annotated and one (1) copy of the approved plan shall be d to the applicant and one (1) copy retained by the department of building ions.
12 13 14 15		(3)		ppeal. If the plan is not approved, the applicant may appeal the staff n to the board of adjustment for a final determination.
16 17	xx17	++++	++++	+++++++++++++++++++++++++++++++++++++++
18 19 20			"Reserv	ved"
21 22	vv18			++++++
23	XX 10	35-38		Manufactured Home And Recreational Vehicle Parks
24 25		(a)		Purpose
26 27 28 29 30 31 32 33 34	xx18	recreati possible protect provide adjoinir manufa	ional veh e common and proped agains ng street	this division is to achieve orderly development of manufactured home and nicle parks, to promote and develop the use of land to assure the best unity environment in accordance with the master plan of the city, and to mote the health, safety and general welfare. Adequate protection shall be st any undesirable off-site conditions or any adverse influence from s or areas. Throughout this division references and provisions relating to nome parks shall also apply to recreational vehicle parks unless ed.
35 36 37 38	xx19,	xx20, : 35-38 (c)		xx22 ++++++++++++++++++++++++++++++++++
39 40	xx19	(2)	Stand	Requirements.
41 42 43 44				f the manufactured home stand requirements set forth in this division is to following:
45 46 47	xx20	A.		al placement of a manufactured home on its stand by means of a car or or truck.
48 49 50	xx21	B.		on of the manufactured home on the stand in a stable condition and a story relationship to its surroundings.
51 52 53 54	xx22	C.		al removal of the manufactured from the lot by means of a car, conveyor or other customary moving equipment.

1 2	xx23			++++++++++++++++++++++++++++++++++++++
3				
4	xx23	(f)	All bu	illding elevations shall be of finished quality.
5		• •		
6				
7	xx24	througl	h xx29	+++++++++++++++++++++++++++++++++++++++
	,,,, <u> </u>	35-38		
8		33-30	00	Radio, Television Antenna, and Wireless
9				Communication Systems
10		(b)	Radio	and Television Antenna
11		(1)	Heigh	it.
12		(.)		
13	xx24	The he	sight of a	n antannae chall he the total maximum to which it is canable of being
14	XX24			n antennae shall be the total maximum to which it is capable of being
				I be measured from the finished grade adjacent to the antenna or antenna
15				re if ground-mounted or from the peak of the roof if roof-mounted.
16				n nonresidential districts shall comply with the height and setback
17				or the particular district. Further, All antenna and antenna support
18				comply with the height restrictions of the joint airport and airport hazard
19				ons, of this Article. All antenna and antenna support structures shall
20				height restrictions of the joint airport and airport hazard zoning
21		regula	tions, Div	rision 4 this chapter, (35-331 Airport Hazard Overlay District (AHOD)).
22				
23		(d)	Wirele	ess Communication Systems
24		(5)		Review.
25		(0)	· · · · · ·	110110111
26	xx25	Antenr	าล รมทกก	rt structure towers are prohibited if they are: within two hundred (200) feet
27	AALU			onio River; or within two hundred (200) feet of a historic landmark; or within
28				00) feet of a historic district or River overlay district; or within a historic
29				overlay district. In conjunction with consideration by the zoning
30				e application for city council approval may be presented to the Historic
31				view Commission (HDRC) if the antenna support structure is located
32		within	two nunc	lred (200) feet of the Riverwalk or within a historic district.
33				
34		(e)	Wirele	ess Communications Systems permitted by Right
35				
36	xx26	(4)	The his	storic preservation officer shall review the permit request if the proposed
37		` ,		s communication system is located within two hundred feet (200) of the
38				alk or within a historic district. The permit request may be presented to the
39				Design and Review Commission (HDRC) for a recommendation if the
40				a support structure is located within two hundred (200) feet of the
41				alk or a historic landmark or within a historic district.
			TAIVOIV	and of a motorio landmark of within a motorio district.
42		(6)		
43		(f)		ess Communication Systems in Public Right-of-Way
44		(1)	Genera	ally.
45				
46	xx27	Α.	City Pu	blic Service electrical substations and power generation plants shall be
47				ed by the historic and design review commission if they are within two
48				d (200) feet of the river overlay district, or if they are two hundred (200)
49				a historic landmark, if they are within two hundred (200) feet of a historic
50				or if they are within a historic district.
51			GIOTIOI,	S. I. 110, alo maini a motorio diotriot.
52		B.	The roo	quirements set forth in subsections (d)(1), (d)(3), and (d)(5) of this part are
52 53		D .		
				ubsection (d)(6) shall not apply to city public service electrical substations
54			and po	wer generation plants.

- (f) Wireless Communication Systems in Public Right-of-Way
- (4) Prohibitions Regarding the River Walk, Historic Landmarks, and Historic Districts.
- Wireless communication towers shall be prohibited in all zoning classifications if the land, structures, rights-of-way or easement s are owned, leased or used by the city of San Antonio, San Antonio Water system, or City Public Service and are within two hundred (200) feet of the river overlay district, or are within two hundred (200) feet of a historic landmark, or are within two hundred (200) feet of a historic district. The historic preservation officer shall review the permit request and if the proposed wireless communication system is located within two hundred (200) feet of the Riverwalk or within a historic district.

35-389 Relocation of Buildings and Structures

xx29 (c) Certificates of Occupancy

In cases in which structure relocations are permissible, certificates of occupancy shall not be issued by the director of development services until all applicable provisions of (a) above and Chapter 6, Article VII of the City Code and all other applicable requirements for issuance of certificate of occupancy required by deferral, and state law and city charter and ordinances are complied with.

35-395 Temporary Uses

xx30 (e) Religious meetings.

Tent and open air church revivals or meetings may be permitted in nonresidential districts for a maximum period of thirty (30) days between the hours of 8:00 a.m. and 10:00 p.m.

(f) Tents

Tents used for special events may be permitted for a period not to exceed one (1) week.

xx31 35-397 Temporary Common Worker Employer

Temporary common worker employer shall comply with the following requirements.

- (a) Hours of operation shall be limited to the period between 6:00 a.m. and 10:00 p.m.
- (b) A sign shall be prominently displayed on the front of the establishment identifying the hours when workers may apply for jobs.
- (c) The establishment shall provide an indoor waiting area large enough to accommodate the maximum number of workers congregating on the premises at any one time.

1			
2		(d)	The establishment shall provide indoor restroom facilities for the workers.
3		` '	·
4 5		(e)	The establishment shall not permit any loitering on the premises and shall maintain the outside yard area free of trash, litter, and graffiti.
6			
7		35-39	8 to 35-399 Reserved
8			
9			
10	XX32,		xx34 +++++++++++++++++++++++++++++++++++
11		35-413	B PUD Plan
12		(-)	Dublic Heaving
13	xx32	(a)	Public Hearing.
14		l la a a a	when in cities of the DLID plan, the director of planning about distribute coming to
15 16			submission of the PUD plan, the director of planning shall distribute copies to riate city departments and agencies for review. Upon receipt of all required items
17			views, the director of planning shall schedule a public hearing by the planning
18			ssion on the proposed plan and shall provide written notice of the hearing to the
19			s of real property lying within two hundred (200) feet of the PUD boundaries. The
20			shall be mailed at least ten (10) days prior to the public hearing date.
21			
22	xx33	(b)	Plan Approval.
23			
24			ne public hearing the commission may approve the plan as submitted, amend and
25			e the plan as amended, or disapprove the plan. If approved, the plan with any
26 27			ments shall be signed by the chairman and secretary of the commission. A copy of proved PUD plan shall be distributed to the director of building inspections and
28			ppropriate departments/agencies for use in issuing permits.
29		ounor a	ppropriate departments/agentice for dee in localing permits.
30	xx34	(c)	Plan Changes.
31		` '	
32			ons to a PUD plan shall be classified as either substantial ornonsubstantial
33			ments. Nonsubstantial amendments may be approved by the director of planning.
34			ntial amendments shall be considered by the planning commission following the
35			procedure required for the initial approval of the plan, including payment of the plan
36 37		review	fee. The following criteria shall be used to identify a substantial amendment:
38		(1)	A change which would include a land use not previously permitted under the
39		(-)	approved PUD zoning.
40			
41		(`2)	A change which would alter the land use type adjacent to a PUD boundary.
42			
43		(3)	A change which would increase the overall density of the PUD by more than ten
44 45			(10) percent. However, in no instance may the overall density of the PUD exceed
45 46			that permitted by the base zoning district.
47		(4)	A change which the director of planning determines would significantly alter the
48		(')	general character or overall design of the plan.
49			
50			
51	xx35	_	h xx38 ++++++++++++++++++++++++++++++++++
52		35-42	1 Zoning Amendments
53		(e)	Approval Criteria
		` '	· ·


	(7)	Right-of-way dedication.
xx35	A.	When considering a rezoning request initiated by a property owner, the city council may require right-of-way dedication along major thoroughfares and streets which do not meet the minimum right-of-way standards established by Article IV of this chapter. Right-of-way dedication shall be required when the rezoning will change the street classification or increase the amount of traffic on the major thoroughfare or street based on the maximum intensity of the uses permitted in the existing and requested zoning districts.
xx36	B.	A change from either temporary or permanent R-4, RM-4, R-5,R-6, R-20 or MH,to a multiple family residence, business, industrial, business park, or entertainment district zoning classification shall constitute prima facie evidence that an increase in traffic shall occur and require right-of-way dedication. The property owner shall have the right to introduce evidence to the zoning commission and city council to show that the zoning change will not increase traffic; however, the evidence must be based on all uses permitted in the requested zoning classification, not solely on the proposed use of the property.
xx37	C.	The city council may require right-of-way dedication in other zoning changes as traffic and street conditions may warrant.
xx38	D.	The requirement for right-of-way dedication shall not be construed as a condition precedent to the approval of a change in zoning, but shall be a condition precedent to the granting of a building permit and/or certificate of occupancy.
	(8)	Other Factors.
	The c	ity council may consider any other factors relevant to a rezoning application under law.
xx39		++++++++++++++++++++++++++++++++++++++
xx39	(5)	"QD" Special Use Permits
	may a provid	nsidering a request for a special use permit for "QD" zoning, the zoning commission also recommend the application of any or all of the development constraints led for in section 35-350(c) and 35-350(d) of this chapter as well as require more ent adverse effects control than is required by section 16-405 of this code.
xx40		++++++++++++++++++++++++++++++++++++++
xx40	(j)	"SUP" Suffix Designation
	desigr	al use permits granted prior to the effective date of this ordinance shall be renated from a suffix of "SUP" to suffix of "ESUP" (existing special use) to distinguish properties from new special use permits to be designated by the suffix "SUP".

35-423 Specific Use Authorization

had on adjacent property.

- (d) Decision
- (4) Conditions.
- xx41 C. At the time of granting special approval for athletic fields in residential, office or light commercial zones, the council may limit the duration of such use to a time period of not less than two (2) years, so that upon completion of such period as so established by the council, the use of property for such purpose must cease, unless a new special approval is granted by the council after following the same procedures involving notices and hearings as was followed originally and after receipt of recommendations from the zoning commission and a report from city staff concerning violations of any conditions or detrimental effects the use has

- (a) Subdivisions Subject To This Section
- (1) The owner of a tract of land located within the limits or in the extraterritorial jurisdiction of the city who divides the tract in two or more parts to lay out a subdivision of the tract, including an addition to a municipality, to lay out suburban, building, or other lots, or to lay out streets, alleys, squares, parks, or other parts of the tract intended to be dedicated to public use or for the use of purchasers or owners of lots fronting on or adjacent to the streets, alleys, squares, parks, or other parts must have a plat of the subdivision prepared. A division of a tract under this subsection includes a division regardless of whether it is made by using a metes and bounds description in a deed of conveyance or in a contract for a deed, by using a contract of sale or other executory contract to convey, or by using any other method. The division of a tract of land for any of the purposes specified herein does not require a transfer of title of all or part of the tract.
 - The owner of a tract of land situated within San Antonio's corporate limits or extraterritorial jurisdiction shall cause a plat to be made thereof upon a request for utility service or a building permit; or upon dividing the tract in two (2) or more parts to lay out a subdivision of the tract, including an addition to a municipality. to lay out suburban, building, or other lots, or to lay out streets, alleys, squares, parks, or other parts of the tract intended to be dedicated to public use or for the use of purchasers or owners of lots fronting on or adjacent to the streets, alleys, squares, parks, or other parts unless a specific exception to such requirement is provided for in section 35-430(c). A division of a tract under this subsection includes a division regardless of whether it is made by using a metes and bounds description in a deed of conveyance, or in a contract for a deed, by using a contract of sale or other executory contract to convey, or by using any other method. A division of land under this subsection does not include a division of land into parts greater than five (5) acres, where each part has access and no public improvement is being dedicated. For purposes of this subsection, access shall mean a minimum frontage of twenty (20) feet on a platted public or private street.



1 2 3		(d) (3)	Decision Withdra		Application.		
5 6 7 8 9 10 11	xx47	Once filed with the reviewing agency, a plat may be withdrawn provided that a written notice of withdrawal stating the reasons for the request is submitted to the director of development services. The thirty (30) day time limitation shall cease on the date that the notice is received by the director; however, the director may elect to present a withdrawal request to the planning commission for consideration. A plat application shall be void for all purposes if it is withdrawn by the applicant.					
12 13 14 15	xx48		3 Deve		++++++++++++++++++++++++++++++++++++++		
16 17 18 19	xx48	plats of	land wit	hin the c	owing general plans, rules, and ordinances to governdevelopment city and its extraterritorial jurisdiction topromote the health, safety, lfare of the city and the safe, orderly, and healthful development		
20 21 22		(1)	The city	's Maste	er Plan, including all of its component plans.		
22 23 24 25		(2)		blic Serv s service	vice's plans and regulations pertaining to the extension of electric .		
26 27		(3)	San An	tonio Wa	ater System's Waterworks Master Plan.		
28 29		(4)	The Un	ified Dev	velopment Code (Chapter 35 of the City Code).		
30 31 32		(5)	Any app	olicable v	watershed Master Drainage Plan adopted by the city.		
33 34 35	xx49			eals to	++++++++++++++++++++++++++++++++++++++		
36 37	xx49a	(2)	Specia	I Except	tions		
38 39 40 41 42		specifie	d. The g	ranting	be granted for the following uses subject to the conditions of the special exceptions may be revoked if the conditions al exception are not maintained at all times.		
43 44 45 46			Α.		nmercial parking lots. Surface parking lots for nonresidential uses permitted in residential zoning districts subject to the conditions elow:		
47 48 49 50 51				1.	The parking lot shall be used only for the noncommercial parking of private motor vehicles of customers and employees. All other uses, including but not limited to the following, are prohibited: The sale, display, storage, repair, servicing, or dismantling of any vehicles, equipment, or merchandise.		
52 53				2.	The parking of vehicles awaiting repair or service.		
54 55				3.	The parking of trucks over three-fourths (3/4) ton capacity).		

- B. Within the A, R-A, R-1, R-5, R-7, and R-8 districts, noncommercial parking lots may be authorized by the board of adjustment for only those uses permitted by right or which have received special approval of the city council within these districts.
- C. The property on which the proposed parking lot is to be located shall be platted in accordance with Article IV of this chapter
- D. The parking lot shall be properly graded for drainage; surfaced with concrete, asphaltic concrete, or asphalt; and maintained in good condition. The parking lot shall be kept free of weeds, litter, and debris.
- E. Individual parking spaces shall meet the minimum size requirements of Division 6, 35-526 of this article.
- F. No advertising signs shall be permitted on the lot other than signs indicating the owner or lessee of the lot and providing parking instructions. Sign lettering shall be limited to a maximum height of six (6) inches.
- G. The parking lot shall not encroach within the front yard setback and shall maintain a minimum setback of ten (10) feet along all other perimeters adjacent to public streets or residential zones. The board of adjustment may vary the setbacks as necessary to protect the residential neighborhood. Barriers shall be installed to prevent parking within the required setback areas.
- H. Parking lot driveways shall be located to minimize interference with residential traffic. If a parking lot abuts two streets of different classifications (e.g., collector versus local street), access shall be restricted to the street with the higher classification.
- I. Unless specifically authorized by the board of adjustment, the parking lot shall not be used between seven o'clock p.m. and seven o'clock a.m. If authorized to be used at night, the lot shall be properly and adequately lighted. The standards to which the lights are affixed shall not exceed fifteen (15) feet in height and the lighting shall be confined within the boundary lines of the parking lot. The parking lot shall be provided with a gate or other sufficient barrier against vehicle entry during the hours the facility served is closed.
- J. Landscaping.
 - i. All required front, side, and rear setback areas shall be landscaped and attractively maintained. The minimum plant requirements per one hundred (100) linear feet of setback area shall include two (2) canopy trees, four (4) understory trees, and twenty (20) shrubs. In addition the setback areas shall be planted with lawn or evergreen ground cover. Plant requirements shall be applied proportionally to setback areas of less than one hundred (100) feet in length. Existing plants which meet the plant criteria may be counted toward satisfying the landscape requirement.

- ii. In addition to the setback areas, an additional ten (10) square feet of landscaped area shall be provided and maintained for each parking space over twenty-five (25) spaces. This additional landscaped area shall be distributed in islands and medians throughout the interior of the parking lot and shall be protected with barriers to prevent damage from vehicles.
- iii. Required landscaped areas shall be provided with either an underground irrigation system or a water connection within one hundred fifty (150) feet of all landscaping.
- K. The lot shall be provided with a masonry wall or other adequate screening not less than three (3) feet nor more than six (6) feet in height at all lot lines fronting upon or adjoining a residential district. However, the board of adjustment may require such masonry wall or other adequate screening at points other than the property line if it determines such location provides more protection to the neighborhood. The screening or masonry wall shall in all cases surround the parking lot. On a corner lot, the wall or screening shall be erected back of the area designated by this chapter for corner visibility. Wheel guards shall be installed and maintained above ground at all such walls or screening to prevent vehicles from making contact with the walls or screening.
- L. Application for a noncommercial parking lot shall be filed by the owner, lessee, or authorized agent with the department of development services. The application shall be accompanied by a site plan drawn to scale depicting the parking lot layout, proposed driveways, and all landscaping.
- M. Granting of a special exception for a noncommercial parking lot shall be for a definite period of time not to exceed four (4) years, and only after notice and a public hearing as provided in this article for appeals to the board of adjustment. In granting a special exception, the board of adjustment may require the noncommercial parking lot to conform to such other conditions as the board may deem necessary to protect the character of the zoning district in which the lot is located.
- N. Prior to actual use of a noncommercial parking lot, the owner or lessee shall obtain a certificate of occupancy from the department of development services to verify compliance with the conditions of the special exception. If a certificate of occupancy is not secured within six (6) months of the date of approval, the special exception shall be null and void and have no force or effect.
- O. Noncommercial parking lots located in a historic district or landmark site shall conform to the regulations of Article VI Historic Preservation and Urban Design of this code and shall require approval of the parking lot plan from the board of review for historic districts and landmarks prior to construction.
- P. Noncommercial parking lots authorized prior to April 1, 1989 shall comply with the conditions imposed at the time of their approval; however, their certificates of occupancy shall expire on the date of their approval in 1993. The director of the department of development services shall notify the owner/lessee of these previously authorized lots and advise them

that their special exception must be renewed as required by subsection (2)M. above.

- (3) Relocation of any buildings and structures, subject to the following conditions:
 - A. Each house must be comparable in size, in quality of construction and in condition to the average of other houses in the area.
 - B. The applicant will comply with Chapter 6, Article VII of this Code and with other applicable codes and ordinances.
 - C. The use will conform to such other conditions as the board may deem proper in harmony with section 35-3043 hereof.
 - D. Permits may be granted under this subsection for buildings which the city's fine arts commission has found to have historic and/or architectural significance and where said commission has made a favorable recommendation as to the relocation site. Such exceptions shall contain appropriate conditions as to repairs to be made. Provisions of other codes of the city or of other chapters of this Code shall not be waived.
- (4) Beauty shops and barber shops may be permitted in all residential zones established by this chapter subject to the following limitations, conditions and restrictions:
 - A. A site plan shall be submitted indicating the size and location of all structures on the property. In addition, photographs of the structure in which the beauty shop or barbershop is to be located shall be submitted.
 - B. The residential architectural appearance of the structure shall not be changed to that of commercial, although a separate entry for the beauty shop or barbershop shall be permitted.
 - C. Signs advertising the beauty shop or barbershop are not permitted, but a nameplate not exceeding one (1) square foot is permitted when attached flat to the main structure.
 - D. The beauty shop or barbershop shall be located within the main structure on the lot and shall not utilize more than twenty-five (25) percent of the gross floor area of the first floor. In the case of a beauty shop in a duplex, the twenty-five (25) percent gross floor area shall be calculated on one (1) living unit of the duplex. In the case of a beauty shop in an apartment unit the board shall determine the area to be used for said operation.
 - E. The beauty shop or barbershop shall be limited to a one (1) operator shop.
 - F. No person not residing on the premises may be employed in the operation of the beauty shop or barbershop.
 - G. Hours of operation shall be regulated by the board and shall be specified in the minutes of the case.
 - H. That such use will not be contrary to the public interest.

1 2 3 4			I. Granting of the permit for a beauty shop or barbershop in conjunction with a residential use is to be for a definite period of time not to exceed two (2) years, and only after notice and hearings as provided in this chapter for appeals to the board of adjustment.
5 6 7 8 9		(5)	Radio and television antennas. In any residential zoning district, antenna locations and heights other than those authorized by section 35-388 may be permitted subject to the following criteria:
10 11 12 13			A. The applicant must demonstrate that compliance with section 35-388 of this chapter would preclude effective communication and furthermore, such ineffective communication involves factors beyond the control of the applicant.
15 16			B. The applicant must comply with all of the requirements of section 35-388.
17 18 19 20 21 22 23			C. In determining the location or height to be permitted, the board of adjustment shall consider the mass of the antenna, the nature of the materials and design of the antenna, the location of the antenna in relation to setback lines, adjacent properties and power lines, the presence of screening structures or landscaping, and the visual impact of the antenna on adjacent properties and public rights-of-way.
24 25	xx49b) ++	+++++++++++++++++++++++++++++++++++++++
26		35-48	1 Appeals to Board of Adjustment
27 28		(b)	Initiation
20 29 30		(7)	Time Limit for Appeal.
31 32 33 34 35 36 37 38	xx49b	public r zoning by an a (30) da director	ard of adjustment shall set a reasonable time for the appeal hearing and shall give notice of the hearing and due notice to the parties in interest. Appeals to the board of adjustment from any order, requirement, decision or determination made administrative official in the enforcement of this chapter shall be made within thirty by after such order, requirement, decision or determination by filing with the rof the department of development services and with the board of adjustment a of appeal.
40	xx50	++++4	+++++++++++++++++++++++++++++++++++++++
41 42		35-48	1 Appeals to Board of Adjustment
43 44	xx50	(e)	Appeal from Board of Adjustment
44 45 46 47 48			eal from a board of adjustment decision shall be filed pursuant to VTCA Local ment Code § 211.011(b).
49 50	xx51		1 Appeals to Board of Adjustment
51 52 53	xx51	(f)	Postponement of Case

1 2 3		after no	event the zoning board of adjustment postpones a case at the applicant's request, otices has been given; the hearing will not be rescheduled until the postponement exified in Exhibit C has been paid by the applicant.
4 5			
6 7	xx52		h xx58b
8		(e)	Approval Criteria
9 10 11		No vari	iance shall be granted unless:
12 13		1.	the variance is not contrary to the public interest; and
14 15		2. unnece	due to special conditions, a literal enforcement of the ordinance would result in essary hardship; and
16 17 18 19		3. substar	by granting the variance, the spirit of the ordinance will be observed and ntial justice will be done.
20 21 22 23	xx52	4.	such variance will not authorize the operation of a use other than those uses specifically authorized for the district in which the property for which the variance is sought is located.
24 25 26	xx53	5.	such variance will not substantially or permanently injure the appropriate use of adjacent conformity property in the same district.
27 28 29	xx54	6.	such variance will not alter the essential character of the district in which it is located or the property for which the variance is sought.
30 31	xx55	7.	such variance will be in harmony with the spirit and purposes of this chapter.
32 33 34 35 36 37	xx56	8.	the plight of the owner of the property for which the variance is sought is due to unique circumstances existing on the property, and the unique circumstances were not created by the owner of the property and are not merely financial, and are not due to or the result of general conditions in the district in which the property is located.
38 39 40	xx57	9.	the variance will not substantially weaken the general purposes of this chapter of the regulations herein established for the specified district.
41 42 43	xx58a	10.	the variance will not adversely affect the public health, safety or welfare of the public.
44 45 46 47	xx58b	11.	property that is not properly platted shall be subject to the condition that platting shall be accomplished prior to the variance taking effect
48	xx59	& xx6	
49		35-50	4 Stormwater Management
50 51 52 53 54 55		and dis impacts runoff i	propose of this section is to provide adequate measures for the retention, detention stribution of stormwater in a manner that minimizes the possibility of adverse son both water quantity and water quality during development.xx59 Innovative management practices designed to meet the provisions of the UDC, enhance the ge of groundwater, and maintain the function of critical environmental features are

Page 17 of 28

1 2 3 4 5 6 7 8		waters irrepla enviro vulnera source	raged. xx60 The city recognizes that watercourses and their associated sheds within the city of San Antonio's jurisdiction represent significant and ceable recreational and aesthetic resources and contribute to the economic and nmental health of the city. In addition, all of the watersheds within the city are able to concentrated surface water runoff, disturbance of wildlife habitat, nonpoint a pollution and sedimentation resulting from development activities and should be upped in a sensitive and innovative manner.
9	vv61	vv62	& xx63 ++++++++++++++++++++++++++++++++++
10 11	жи,		& xx63 ++++++++++++++++++++++++++++++++++++
12 13		(e)	Site Design and Grading
14 15 16 17 18 19 20 21 22 23		(1)	All land disturbing or land filling activities or soil storage shall be undertaken in a manner designed to minimize surface runoff, erosion and sedimentation, and to safeguard life, limb, property and the public welfare in accordance with the NPDES (TPDES) construction site regulation ordinance, ordinance No. 94002, as amended, and the document entitled "Complying with the Edwards Aquifer Rules; Technical Guidance on Best management Practices, " by Michael E. Barrett, Ph.D., P.E. Center for Research in Water Resources, Bureau of engineering Research, University of Texas at Austin, (RG-348, June 1999), which documents are hereby incorporated by this reference.
24 25 26 27 28	xx61	(2)	Erosion and sedimentation controls in accordance with the specifications established by the director of public works in compliance with the National Pollution Discharge Elimination System permitting requirements for the city are required.
29 30 31	xx62	(3)	Projects shall not be considered complete until restoration has beenmade in accordance with NPDES requirements.
32 33 34 35 36 37	xx63	(4)	Where possible, multiple uses of drainage facilities and open space shall be incorporated by the owner or developer of a new subdivision. Alternative uses such as public recreation, horse/bike/hiking trails, walking paths, nature preserves, wildlife habitat areas, etc. are encouraged subject to the approval of the director of public works.
38 39 40 41 42 43 44 45 46		(5)	A note must be placed on the plat for residential lots, which states that finished floor elevations must be a minimum of eight (8) inches above final adjacent grade. A grading plan shall be prepared and submitted to the city of San Antonio, which indicates typical lot grading for all lots in the subdivision using typical FHA lot grading types (A, B & C). A more detailed grading plan is also acceptable. No more than two average residential lots may drain onto another lot unless a drainage easement is dedicated to contain the runoff.
47	xx64		+++++++++++++++++++++++++++++++++++++++
48			94 Stormwater Management
49		(d)	Drainage easements / Rights-of-way
50 51 52	xx64	(3)	Natural Watercourses or Floodplains.
53		Facom	pents for natural watercourses shall be the 100-year floodolain or the 25-year plus

Page 18 of 28

freeboard (see <u>Table 504-9</u> of this Section) whichever is greater. In floodplain areas

where ongoing maintenance is required or the floodplain will be reserved for use by the public, the drainage easements shall be maintained by a public entity and the property will be dedicated to the city as a multi-use drainage easement. A drivable access way shall be provided in floodplain easements for the length of the easement when regular maintenance of the floodplain is required. Diversion of stormwater away from the natural watercourse will not be allowed except within the boundaries of the property controlled by the developer, provided that the diverted water is returned to the watercourse within which it would naturally have been flowing prior to leaving the developer's property. An analysis of the timing of the diverted hydrograph on watersheds greater than twenty (20) acres, as it reenters the receiving watercourse, must be performed to show that the peak flowrate in the receiving watercourse has not been increased as a result of the diversion.

xx65

35-506 Transportation and street Design

(a) Applicability

D. The owner of any tract of land situated within the corporate limits or the extraterritorial jurisdiction of San Antonio who is required to file a plat shall provide street right-of-way dedication as required by this article.

(a) Applicability

(2) Building Permit Requirements.

xx66 E. Variance

A variance to the requirements of this section may be granted by the planning commission if the commission finds that there are special circumstances or conditions, unique to the land involved, such that strict application of these requirements would be unreasonable and the granting of the variance would not be detrimental to the public health, safety, or welfare. Application for a variance shall be submitted in writing to the director of planning accompanied by the variance fee specified in Exhibit C to this chapter and an eight and one-half by eleven (81/2 X 11) inch site plan indicating the location of the variance request and the location of existing sidewalks and curbs within a two thousand (2,000) foot radius.

xx67 (2) Street Layout

The arrangement, character, extent, width, grade and location of all streets shall conform to the Master Plan and the Major Thoroughfare Plan and shall be considered in their relation to existing and planned streets, to topographical conditions, to public safety and convenience, and in their appropriate relation to the proposed uses of the land to be serve by such streets. The street layout shall be devised for the most advantageous development of the entire neighborhood development.

1	xx68	(3) Sta	andard Street Cross Sections
3 4 5 6			bdivider shall develop the streets for the subdivision in accodance with the im standards in Section (d) following.
7 8 9 10 11	xx69	_	h xx71 ++++++++++++++++++++++++++++++++++
12 13		(11)	Safety Lanes
14 15 16 17 18 19 20	xx69	A.	Safety lanes shall be required when the planning commission determines that adequate access for safety is not provided within or into the subdivision. The planning commission shall consider the recommendations of the fire chief and/or police chief of the city in making their determinations. These additional safety lanes shall be delineated and designed as safety lanes on the appropriate plat(s) required by this chapter. The design standards and construction specifications of safety lanes shall be one of the following:
22 23 24			 In accordance with the safety lane standards and specifications described in Exhibit A.
25 26 27 28			 An unpaved, all-weather surface and base with a minimum width of twenty (20) feet capable of supporting heavy vehicles, e.g., fire-fighting apparatus, and meeting with the approval of the director of public works.
29 30 31 32 33 34	xx70	B.	All private safety lanes shall be owned and maintained by a corporation, community association, or other legal entity as established for this purpose. The legal entity shall provide the city with written permission for access at any time without liability when on official business, and further to permit the city to remove at any time any and all obstructions of any type in safety lane and to assess the costs of removal to the owner(s) of the obstruction.
36 37 38	xx71	C.	The city shall not be liable for damage to underground utilities beneath designated safety lanes caused by heavy city vehicles.
39 40 41 42 43	xx72		++++++++++++++++++++++++++++++++++++++
+3 44 45	xx72		ct is subdivided into parcels larger than ordinary building lots, such parcels shall be
46 47 48			ed to allow the opening of future streets and logical further subdivision.
49 50 51 52	xx73	& xx74 35-50 (g)	++++++++++++++++++++++++++++++++++++++
53	xx73	(4)	Arterial Streets

1 2 Where a primary or secondary arterial street, as shown on the Major Thoroughfare Plan, 3 traverses or is contiguous with an area being platted, such primary or secondary arterial 4 street shall be platted in the location and of the width indicated by the requirements of the 5 Major Thoroughfare Plan and these regulations. In no event shall an area be platted so as to leave a narrow strip of land which is unsuitable as a building site, unmarketable, or 6 is undevelopable (as these terms are commonly known) and which is excluded from 7 8 plating for the purpose of circumventing these requirements. 9 10 xx74 (5) **Marginal Access Streets** 11 12 Marginal access streets should be located parallel to and adjacent to an arterial street. 13 14 15 35-506 Transportation and street Design 16 (h) Street Names & Signage 17 18 19 xx75 (5) Street Name Changes 20 21 Requests for street name changes within the city limits shall be submitted to the city 22 clerk. An application processing fee as specified in Exhibit C shall be paid to the director 23 of development services for each street name change request prior to consideration of the request by the city council. Additionally, an installation fee as specified in Exhibit C for 24 25 each sign that needs to be changed per each street intersection shall also be paid prior to 26 the city council consideration. The installation fee shall be refunded if the request is not 27 approved. 28 29 30 35-506 Transportation and street Design 31 **Private Streets** (i) 32 33 34 **xx76** (6) **Parking on Private Streets** 35 36 Parking on private streets shall be prohibited on any private street less than twenty eight 37 (28) feet in width and if utilized on streets thirty (30) feet wide or wider, it must be clearly 38 distinguishable from the movement lanes. 39 40 35-506 Transportation and street Design 41 (r) **Access and Driveways** 42 43 44 Single-Family Residential Subdivisions. (2) 45 46 xx77 Where a subdivision abuts a major thoroughfare, lots for single-family residential Α. 47 use in the ETJ or in residential zoning districts shall not front on the thoroughfare, 48 the sole exception shall be lots greater than one (1) acre in size which provide for 49 permanent vehicular turn around on the lot to prevent backing onto the

thoroughfare and this restriction should be noted on the plat. Access points

the thoroughfare shall be prohibited. However, if conditions are such that

which would permit vehicular access to such lots less than one acre in size from

vehicular access to such lots cannot be provided other than from the collector or

arterial street, the director of development services may permit the creation of a

50

51

52

53

1 marginal access street or easement to serve two (2) or more lots. The marginal 2 access street or easement shall be designed to permit entry to the thoroughfare 3 without requiring a motorist to execute a backing maneuver. Marginal access 4 streets or easements shall be included on the subdivision plat. 5 B. 6 Marginal access streets 7 8 Where the subdivider furnishes a marginal access street on the subdivision side of a 9 primary or secondary arterial, he shall not be required to furnish any pavement, curbs, or sidewalks for the primary or secondary arterial. 10 11 12 13 35-507 Utilities 14 15 (d) Water, Wastewater and Recycled Water Systems 16 17 xx78 (1) Generally. 18 19 All subdivisions within the city and its extraterritorial jurisdiction shall be provided with 20 water and wastewater systems. Water, waste water recycled water systems shall be 21 installed in accordance with the utility service provider's "utility service regulations." 22 23 The regulation for water service, system extension, and service line installation adopted 24 by the applicable utility provider and the criteria for water supply and distribution in the 25 city and its extraterritorial jurisdiction are hereby adopted as a part of the city planning 26 area subdivision regulations and are on file tin the office of the city clerk. 27 28 29 35-507 Utilities 30 31 (d) Water, Wastewater and Recycled Water Systems 32 33 xx79 Unsewered Lots. (4) 34 35 Where an organized sanitary sewer collection system is not provided, the lot size shall be 36 determined in accordance with the requirements of the Bexar County Commissioners Court order "Regulating and Licensing of Private Sewage Facilities," and shall be 37 38 approved by the county director of public works prior to approval by the planning 39 commission. Planned unit developments shall not be permitted with septic tank system 40 installations unless approved by the county director of the public works. If approved, the 41 septic tank system shall serve only one (1) lot and shall be located on that lot. 42 43 xx80, xx81 & xx82 44 35-507 Utilities 45 **Municpal Utility Districts** 46 (h) 47 48 **08xx** (1) Policy 49

The stated policy of the City of San Antonio as contained in Resolution Number 86-29-83, passed by the city council on June 26, 1986, is to discourage the formation of municipal utility districts or other special districts. It is prudent for the city to consent to the creation

50

51

of such districts under certain circumstances. The city's goal is to limit the extent of its financial liability in all such cases.


xx81 (2) Guidelines.

The city manager and the city staff are hereby authorized to enter into negotiations for consent agreements which the promoters of proposed districts when such consent is in the city's best interests. The city council hereby adopts the following guidelines and negotiation goals for developing such agreements.

- A. Developer shall secure the wastewater discharge permit.
- B. Developer shall establish costs for a state approved municipal water system.
- C. A limit shall be set on the dollar amount of the bonds issued.
- D. Developer's contribution shall be increased beyond the thirty (30) percent set in the Texas Code.
- E. A time limit shall be set on debt retirement.
- F. Proceeds from bond sales are to be used only for water and sewer facilities.
- G. An exofficio member of the municipal utility district board of directors is to be appointed by city council.
- H. Thirty (30) days notice of proposed bond issue (sale) must be given to the city clerk.
- I. A copy of the municipal utility district's annual report to the Texas Water Commission must be given to the city clerk.
- J. The municipal utility district shall not provide water or wastewater service to any tract unless the planning commission has approved a plat for that tract and the plat has been recorded in the county deed records.
- K. The municipal utility district shall not provide services outside its boundaries unless specifically approved by city council.
- L. No land may be annexed into a district without city council approval.
- M. All right-of-way, public park land, utility and drainage easements must be dedicated to the district.
- N. All development and public improvements within the district must conform to city codes and regulations; all plans and construction for public improvement projects must be approved by city inspectors.
- O. Developer must run a financial feasibility analysis on the city model.
- P. A limit shall be established on the amount allowed for a professional services contract.

xx82 (3) Negotiation Goals

1 2 These negotiation goals are not meant to be all-inclusive and staff may amend as 3 necessary in the city's best interests. 4 5 6 **xx83** 35-602 Administration 7 **Notification of Affected Property Owners** 8 (a) 9 10 Prior to historic and design review commission consideration of any property for historic 11 designation, or removing or upgrading the designation of historic, as it applies to a district 12 or landmark, the historic preservation officer shall send notice of the fact by mail to the owner or owners of affected property, stating reasons for recommendation. Upon 13 14 passage of any ordinance designating as historic, or removing or upgrading the designation of historic, as it applies to a district or landmark, the city clerk shall send 15 16 notice of the fact by mail to the owner or owners of affected property. This action shall be 17 in addition to notice given prior to public hearing as set forth under the city's zoning code. 18 19 xx83 Property owners within a proposed historic district boundary shall be notified prior to 20 historic and design review commission hearing on the historic district designation. Upon 21 recommendation of the commission, the proposed historic district designation shall be 22 submitted to the zoning commission for its review and recommendation. The zoning 23 commission shall give notice, conduct its hearing, and make recommendations to the city 24 council in the same manner and according to the same procedures as specifically 25 provided in the general zoning ordinance of the City of San Antonio. In like manner, the 26 city council shall give notice, follow the publication procedure, hold hearings, and make 27 its determination in the same manner as provided in the general zoning ordinance of the 28 City of San Antonio. 29 30 xx84 31 32 35-614 Demolition (b) **Unreasonable Economic Hardship** 33 34 Criteria. (3) 35 36 37 xx84 K. In the event that any of the required information is not reasonably available to the applicant and cannot be obtained by the applicant, the applicant shall file with his 38 39 affidavit a statement of the information which cannot be obtained and shall 40 describe the reasons why such information cannot be obtained. 41 42 43 xx85a through xx88 35-614 Demolition 44 (d) **Documentation & Strategy** 45 46 47 xx85a (1) Applicants that have received a recommendation for a certificate shall document 48 buildings, objects, sites or structures which are intended to be demolished with 49 35mm slides or prints, preferably in black and white, and supply a set of slides or 50 prints to the historic preservation officer. 51



3 xx92 & xx93 4 35-712

(b) Vested Rights Recognition Process

xx92 (3) Basis for Permit Rights

The following criteria will be used by the city in determining the existence of rights for projects initiated after September 1, 1997. The following permits may be relied on by a property owner or developer to establish permit rights for property that is the subject of the permit. Provided, however, a minor plat that plats only easements shall not confer any permit rights. The permit rights acquired in reliance on (1) of the types of permits indicated below will expire unless the action required to maintain permit rights is taken within the time frame indicated for each permit type.

A. Preliminary overall area development plan (POADP)

Permit rights will be recognized on the property which is the subject of a POADP that has been approved by the city planning department. The permit rights recognized for property located with an approved POADP will expire unless a final plat is approved within eighteen (18) months from the approval of the POADP that plats, at least eight (8) percent of the net area of the POADP area or that requires at least five hundred thousand dollars (\$500,000.00) in infrastructure expenses if the POADP is one thousand (1,000) acres or less or at least one million dollars (\$1,000,000,00) if the POADP is more than one thousand (1,000) acres. Further, the permit rights for property within an approved POADP will expire unless fifty (50) percent of the net area with the approved POADP is the subject of final plats or development within ten (10) years from the date of approval of the POADP. The remaining fifty (50) percent must obtain final plat approval or be developed within ten (10) years after the initial fifty (50) percent of the net area within the POADP has been platted or developed Unless specific provisions to the contrary exist in an individual ordinance or city code provision, the filing of an amending POADP, plat or replat will not result in a loss of permit rights provided that the required area of acreage within the POADP platted or value of infrastructure expenses do not fall below the amounts indicated above as a result of the amendment or replat.

B. Plat Applications

Permit rights will be recognized on the property that is the subject of a plat application that has been filed with the city planning department, provided all necessary platting fees have been paid. The rights recognized for property located within such a plat application will expire unless the plat application is heard by and approved by the director of planning or the planning commission within eighteen (18) months from the date the plat application is filed with the city planning department.

C. Plats

Permit rights will be recognized on the property which is the subject of a plat that has been approved by the city planning commission or director of planning. The permit rights recognized for property located within an approved plat will expire unless the plat is recorded tin the Bexar County Deed Records within three (3)

1 years from the date of approval by the city planning commission or director of 2 planning. 3 4 D. **Building Permits** 5 A building permit may be relied on as a basis for permit rights for property 6 identified in the site plan submitted to the city as part of the building permit 7 8 application. However, rights that are base on a building permit will expire unless 9 construction authorized by the building permit is begun within sic (6) months from the date the building permit is issued. 10 11 12 **x**x93 E. Permit Rights Conferred 13 Permits rights conferred by this section shall not extend beyond the time periods 14 15 prescribed herein except by the granting of a variance from the time limits as provided herein. Under no circumstances shall the extension of a time limit 16 17 extend the permit rights conferred herein except through the variance provision 18 of this section. 19 20 21 xx94 & xx95 35-801 Board of Adjustment 22 (k) Findings of Fact 23 24 25 xx94 (1) Power to Make Exceptions. 26 27 The zoning board of adjustment may make special exceptions to the terms of this chapter 28 only as provided in Divison 7 of Article III this chapter; however, the board shall not grant 29 a special exception unless it makes specific findings that: 30 31 Α. The exception will be in harmony with the spirit and purposes of his chapter. 32 33 B. The public welfare and convenience will be substantially served. 34 35 C. The neighboring property will not be substantially injured by such proposed use. 36 37 D. The exception will not alter the essential character of the district and location 38 which the property for which the exception is sought. 39 40 E. The exception will not weaken the general purpose of this chapter or the 41 regulations herein established for the specific district. 42 43 xx95 (2) **Record of Action** 44 45 The above findings of the board shall be incorporated into the official minutes of the 46 board meeting in which the special exception is authorized. 47 48 xx96 & xx97 49 50 35-B121 Subdivision Plat Application Contents 51 (c) 52 53 **xx96** (19)Plat name. The term "planned unit development" shall be included in the name 54 of each plat.

xx97

20) Plat notation. A plat which includes common areas or facilities to be maintained by a community association shall be annotated with the following note:

"A legal instrument establishing a plan for the use and permanent maintenance of the common areas/facilities designated on this plat is being recorded on the same date as this plat".